

STORRS COURT SUBDIVISION

LOCATED IN THE SOUTHWEST QUARTER OF SECTION 23, TOWNSHIP 5 SOUTH, RANGE 1 EAST,

SALT LAKE BASE AND MERIDIAN





PROPERTY DESCRIPTION:

A TRACT OF LAND BEING SITUATE IN THE SOUTHWEST QUARTER OF SECTION 23. TOWNSHIP 5 SOUTH, RANGE EAST, SALT LAKE BASE AND MERIDIAN, HAVING A BASIS OF BEARINGS OF NORTH 03°29'19" EAST BETWEEN THE REFERENCE TO THE WEST QUARTER AND THE NORTHWEST CORNER OF SECTION 23, TOWNSHIP 5 SOUTH, RANGE 1 EAST, SALT LAKE BASE AND MERIDIAN, SAID TRACT OF LAND BEING MORE PARTICULARLY DESCRIBE

BEGINNING AT A POINT WHICH IS SOUTH 578.93 FEET AND SOUTH 89'13'09" EAST 2383.76 FEET FROM THE REFERENCE TO THE WEST QUARTER OF SAID SECTION 23, SAID POINT ALSO BEING THE SOUTHEAST CORNER OF LOEFLER PARK TWN HOMES SUBDIVISION, PLAT "A", ON FILE WITH THE OFFICE OF THE UTAH COUNTY RECORDER AS MAP NO. 15224, AND RUNNING THENCE ALONG SAID SUBDIVISION THE FOLLOWING THREE (3) COURSES, 1) NORTH 00°44'00" EAST 433.40 FEET, 2) WEST 15.64 FEET, 3) NORTH 11.71 FEET TO THE PROLONGATION OF A FENCE LINE, SAID POINT BEING AT THE POINT OF BEGINNING OF THAT CERTAIN PROPERT BOUNDARY LINE AGREEMENT ON FILE WITH THE OFFICE OF THE UTAH COUNTY RECORDER AS ENTRY NO. 74491: 2023; THENCE SOUTH 89"01"03" EAST ALONG SAID PROPERTY BOUNDARY LINE AGREEMENT A DISTANCE OF 249.94 FEET TO A POINT ON A PROLONGATION OF THE WEST FACE OF A RETAINING WALL; THENCE SOUTH 00°02'56" WEST ALONG SAID PROPERTY BOUNDARY LINE AGREEMENT A DISTANCE OF 86.50 FEET TO THE PROLONGATION OF A FENCE LINE, SAID POINT ALSO BEING ON THE PROLONGATION OF THE WEST LINE OF PLA "A". GIBB SUBDIVISION. ON FILE WITH THE OFFICE OF THE UTAH COUNTY RECORDER AS MAP FILING NO. 1860; THENCE SOUTH 01'06'00" WEST ALONG SAID FENCE AND PROLONGATION THEREOF, PROPERTY BOUNDARY LINE AGREEMENT AND A PROLONGATION THEREOF, SUBDIVISION AND PROLONGATION THEREOF A DISTANCE OF 257.5. FEET TO THAT CERTAIN PROPERTY BOUNDARY LINE AGREEMENT ON FILE WITH THE OFFICE OF THE UTAH COUNTY RECORDER AS ENTRY NO. 70891: 2023; THENCE ALONG SAID PROPERTY BOUNDARY LINE AGREEMENT THE FOLLOWING TWO (2) COURSES, 1) NORTH 89"13" O9" WEST 75.00 FEE, 2) SOUTH 01"06" OO" WEST 100.00 FEET TO THE NORTH RIGHT-OF-WAY LINE OF 400 SOUTH STREET; THENCE NORTH 89"13" WEST ALONG SAID RIGHT-OF-WAY LINE A DISTANCE OF 157.90 FEET TO THE POINT OF BEGINNING.

CONTAINING 96,752 SQUARE FEET OR 2.221 ACRES, MORE OR LESS.

BASIS OF BEARINGS:

THE BASIS OF BEARINGS FOR THIS SURVEY IS NORTH 03'29'19" EAST BETWEEN THE REFERENCE TO THE WEST QUARTER AND THE NORTHWEST CORNER OF SECTION 23, TOWNSHIP 5 SOUTH, RANGE 1 EAST, SALT LAKE

OWNER'S DEDICATION

KNOW ALL BY THESE PRESENTS THAT WE, THE UNDERSIGNED OWNERS OF THE DESCRIBED TRACT OF LAND HEREON, HAVING CAUSED THE SAME TO BE SUBDIVIDED INTO LOTS TO HEREAFTER BE KNOWN AS STORRS COURT SUBDIVISION

DO HEREBY DEDICATE FOR PERPETUAL USE OF THE PUBLIC ALL PARCELS OF LAND SHOWN ON THIS PLAT AS INTENDED FOR PUBLIC USE, AND DO WARRANT, DEFEND, AND SAVE THE CITY HARMLESS AGAINST ANY EASEMENTS OR OTHER ENCUMBRANCES ON THE DEDICATED STREETS WHICH WILL INTERFERE WITH THE CITY'S USE, OPERATION, AND MAINTENANCE OF THE STREETS AND DO FURTHER DEDICATE THE EASEMENTS AS SHOWN FOR THE USE BY ALL SUPPLIERS OF UTILITY OR OTHER NECESSARY SERVICES. January 23, 2025

ACKNOWLEDGMENT:

STATE OF UTAH COUNTY OF <u>Utah</u>

ON THIS 23 DAY OF January ... A.D. 2025 PERSONALLY APPEARED BEFORE ME

Ross Mitchell , who being duly sworn of Affirmed, did say that (s) he is the Vice President

SIGNED BY HIM/HER ON BEHALF OF SAID LLC BY AUTHORITY OF ITS BYLAWS, OR BOARD OF DIRECTORS, AND THAT SAID CORPORATION EXECUTED THE SAME.

Stephanie Finau

Stephanie Finau
PRINTED NAME, A NOTARY PUBLIC COMMISSIONED IN UTAH

735014


January 11, 2028

ADMINISTRATIVE APPROVAL AUTHORITY

THE ADMINISTRATIVE APPROVAL AUTHORITY OF AMERICAN FORK CITY, COUNTY OF UTAH, HEREBY APPROVES THIS SUBDIVISION ON THIS _______, A.D. 2024.

STORRS COURT SUBDIVISION

LOCATED IN THE SOUTHWEST QUARTER OF SECTION 23, TOWNSHIP 5 SOUTH, RANGE 1 EAST, SALT LAKE BASE AND MERIDIAN AMERICAN FORK CITY, UTAH COUNTY, UTAH





801.553.8112 WWW.WILDINGENGINEERING.COM

3. LOWEST FLOOR SLAB ELEVATION MUST BE A MINIMUM OF 3 FEET ABOVE WATER LEVEL

INSTALLED AND 2) FIRE HYDRANTS ARE INSTALLED, APPROVED BY THE FIRE MARSHALL AND

NO3'29'19"E 2637.70' (MEAS, MON TO MON) -

N77"14'50"W 145.35' (CALC) -

Curve Table

89'40'51"

8.30' | 15.00' | 31'41'30" | N07'31'30"W |

33.85' | 63.00' | 30'47'04" | N07'58'43"W

28'06'00"

28'43'19"

93'42'06"

80.90' | 63.00' | 73'34'18" | \$42'24'56"W

18.47' | 15.00' | 70°32'49" | \$43°35'37"W

C11 | 310.70' | 63.00' | 282'34'20" | S62'05'05"E C12 | 30.75' | 244.00' | 7'13'15" | S04'42'38"W

C13 34.66' 275.00' 7'13'15" \$04'42'38"W

30.45' | 63.00' | 27'41'32" |

30.90'

103.03'

31.58' 63.00'

Chord Bearing | Chord Distance

N21"15'35"E

N77"34'01"E

8.19"

33.44

30.59

31.25'

91.93'

75.45

17.32

30.73

This map is provided solely for the purpose of assisting in locating the property and Cottonwood Title Insurance Agency, Inc. assumes no liability for variation, if any, with any actual survey.

N89°13'09"W 157.90'

400 SOUTH STREET (PUBLIC WAY)

REFERENCE DOCUMENTS

NOTICE OF INTEREST, BUILDING REQUIREMENTS, AND ESTABLISHMENT OF RESTRICTIVE COVENANTS; RECORDED IN THE OFFICE OF THE UTAH COUNTRY RECORDER AS

SEWER AND WATER AUTHORITY APPROVAL

APPROVED THIS 4 DAY OF Jure, A.D. 2024, BY THE WATER AUTHORITY.

SEWER AND WATER AUTHORITY

U/4/24
DATE



SURVEYOR'S SEAL

RECORDER'S OFFICE

ENT 6539: 2025 MARCH 19593 ANDREA ALLEN UTAH COUNTY RECORDER 2025 Jan 29 02:11 PM FEE 68,00 BY KR RECORDED FOR AMERICAN FORK CITY